

J Warren
Ardwyn, High St
St Dogmaels, Cardigan
Pemb SA43 3EF

TEL 01239621836

ESTIMATE

ST DOGMAELS COMMUNITY COUNCIL

BUS SHELTER, THE MOORINGS

TO TEMPORARY COVER OFF BUS SHELTER WHILE

WORKS IN PROGRESS.

TO CLEAN AND REPAIR APPROX 23MTR² OF INNER

AND OUTER WALLS INCLUDING ROOF AREA FOR DARK

OAK PRESERVATIVE.

TO CLEAN AND PREPARE SEATING FOR PRESERVATIVE.

TO PAINT FUTURE STORAGE APPROX 23MTR² WITH

TWO COATS OF DARK OAK PRESERVATIVE.

LABOUR AND MATERIAL COST

£ 384-00

ESTIMATE

ST DOGMAELS COMMUNITY COUNCIL
BUS SHELTER ADJACENT TO B V REES ABBEY GARAGE

- TO TEMPORARY CORDON OFF BUS SHELTER WHILE WORKS IN PROGRESS.
- TO REPAIR AND CORNERS OF FASCIA BEARDS AND REPLACE 4 LIN MTRS OF FASCIA.
- TO PAINT FASCIA AND SOFFITS WITH PRIMER WHERE NEEDED, 2ND COATS OF UNDERCOAT AND 1ND COAT OF BLACK FINISH.
- TO SUPPLY AND FIT GUTTERING AND DOWNPIPES IN BLACK PVC APPROX 9 LIN MTRS OF GUTTERING, APPROX 6 LIN MTRS OF DOWNPIPE INCLUDING BRACKETS AND CLIPS.
- TO TAKE AWAY EXISTING WASTE TO DISPOSAL.
- TO FORM 10MM PLYWOOD CEILING INCLUDING NOGGIN'S WHERE NEEDED, PRIME AND APPLY 2ND COATS OF WHITE VINYL SILK EMULSION APPROX 8 MTR².
- TO PREPARE AND PAINT SLATTED SERTING, WITH 2ND COATS OF UNDERCOAT AND 2ND TOP COAT IN BLACK FINISH.
- TO PAINT INTERIOR AND EXTERIOR MASONARY WALLS APPROX 40 MTR² WITH 2ND COATS OF WHITE MASONARY PAINT INCLUDING PRE PREPARATION. (HAND BRUSH ONLY DUE TO CARS IN CLOSE VICINITY)

MATERIAL AND LABOUR COST

£2,190-00